

Sub: Status of tenders dealt by SBU-33 as on 31.03.2021

S.No.	Tender No.	Item / Nature of Work	Mode of tender enquiry	Date of publication of NIT / LIT	Type of bidding (Single/ two bid system)	Last date of receipt of tender	No. of tenders recd	Nos. & Names of Parties qualified after technical e-valuation	No. & Name of Parties not qualified after tech. e-valuation	Whether contract awarded to lowest tender / evaluated L1	LOA or Work Order No. Dated:	Name & Address of contractor	Value of Contract (in Rs.)	Scheduled date of completion of supplies / work	Payment details
	1	2	3	4	5	6	7	8	9	10	11	12	13.00	14	
SBU 33 (HIGHWAY/KOLKATA)															
1	04/LT/RITES-HW/KOL/RT330-00040/2019 Dt.28.02.2019	Preparation of GAD, details design and drawing and BOQ for 35 nos. RCC bridges in the district of the state of west bengal	Limited	28.02.2019	Single	11.03.2019	3 no. tender recd.	1. M/s. BABTECH 167A, RAJA DINENDRA STREET, 1ST FLOOR, KOLKATA-700004 2. M/s. M S CONSULT, CONSULTING ENGINEERS, FLAT NO. 1G, 313 CANAL STREET, KOLKATA 700048 3. M/s. CONSTEEL CONSULTANTS PVT. LTD., CF-38, SALT LAKE, SECTOR-I, KOLKATA-700064	NIL	Awarded	Work Order No. RITES/HW/KOL/RT330-00040/2019/32 2 issued on 11.04.2019	M/s. M S CONSULT, CONSULTING ENGINEERS, FLAT NO.1G, 313 CANAL STREET, KOLKATA700048	995,000.00	45 DAYS FROM THE DATE OF ISSUE OF WORK ORDER	Final Bill processed
2	07/LT/RITES/HW/KOL/Sonarpur& Prince anwar shah connector flyover/Geotechnical Investigation Dt.02.05.2020	GEOTECHNICAL INVESTIGATION FOR PREPARATION OF DPR IN CONNECTION WITH CONSTRUCTION OF a two lane flyover from sonarpur Bantala road to sonarpur -chakraberia road south 24pgs and construction of elevated corridor along east west direction from prince anwar shah connector via jibanananda setu to deshapran sasmal road near tipu sultan masjid.	Limited	02.05.2019	Single	15.05.2019	3 no. tender recd.	1. M/s. CONSTEEL CONSULTANTS PVT. LTD., CF-38, SALT LAKE, SECTOR-I, KOLKATA-700064 2. M/s. CHATTERJEE CONSTRUCTION CO. KULTI, BURDWAN,713343 3. M/s. TECHPRO ENGINEERS PVT. LTD., 103, RATAN DHAM 208001.	NIL	Awarded	Work Order No. RITES/HW/KOL/RT330-00045&47/Geo technical investigation/49 6 issued on 04.06.2019	M/s. CHATTERJEE CONSTRUCTION CO. KULTI, BURDWAN,713343	1,065,109.50	45 DAY DAYS FROM THE DATE OF ISSUE OF WORK ORDER	2nd RA bill @40% paid

Sub: Status of tenders dealt by SBU-33 as on 31.03.2021

S.N o.	Tender No.	Item / Nature of Work	Mode of tender enquiry	Date of publication of NIT / LIT	Type of bidding (Single/ two bid system)	Last date of receipt of tender	No. of tenders recd	Nos. & Names of Parties qualified after technical e-valuation	No. & Name of Parties not qualified after tech. e-valuation	Whether contract awarded to lowest tender / e-valuat-ed L1	LOA or Work Order No. Dated:	Name & Address of contractor	Value of Contract (in Rs.)	Scheduled date of completion of supplies / work	Payment details
	1	2	3	4	5	6	7	8	9	10	11	12	13.00	14	
SBU 33 (HIGHWAY/KOLKATA)															
3	03/OT/RITES/HW /KOL/GT/RUBY/2 019 Dt. 14/08/2019	Geotechnical Investigation work for preparation of fesibility report cum DPR regarding the work of Pedestrain underpass and flyover at Ruby More.	Open	26.08.2019	Single	26.08.2019	08 no. tender recd.	1. M/s. ARUN SOIL LAB PRIVATE LIMITED,E-11,First Floor, Lekhraj Market - 1, Indra Nagar Lucknow-226016. 2. M/s. Techpro Engineers Pvt Ltd. 103, Ratan Dham, 12/483 ,Microberts Gnaj, Kanpur - 208001. 3. M/s. SUPERINTENDENCE CO OF INDIA Pvt Ltd.76 Everest House ,46C, Chowringhee Roqd. Calcutt-700017. 4. M/s. PIONEER SURVEYORS, Pioneer Tower,Premises No.20-085,Street No.85,Block:AB-109,Action Area. Opp.Tank No.2, New Town Rajarhat,North 24Praganas.West Bengal - 700156. 5. M/s. BHASKRAM JYOTISH ANUSANDHAN KENDRA, Shop No. 03, Gokuldhm CHS LTD, Sukapur,New Panvel District, Raigad, Maharashtra - 382421. 6. M/s. B.G. GEOTECH Pvt Ltd.32/B,Pearabagan Bye Lane, Konnagar,Uttarpara Hooghly - 712235.	NIL	Awarded	Work Order No. RITES/HW/KO L/RT330-00049/GT/116 5 on 06.12.2019	M/S BHASKRAM JYOTISH ANUSANDHAN KENDRA, Shop No. 03, Gokuldhm CHS LTD, Sukapur,New Panvel, District- Raigad, Maharashtra - 382421.	997,556.78	60 DAY DAYS FROM THE DATE OF ISSUE OF LoA/WO	2nd R.A Bill paid on 19.08.2020

Sub: Status of tenders dealt by SBU-33 as on 31.03.2021

S.N o.	Tender No.	Item / Nature of Work	Mode of tender enquiry	Date of publication of NIT / LIT	Type of bidding (Single/ two bid system)	Last date of receipt of tender	No. of tenders recd	Nos. & Names of Parties qualified after technical e-valuation	No. & Name of Parties not qualified after tech. e-valuation	Whether contract awarded to lowest tender / evaluated L1	LOA or Work Order No. Dated:	Name & Address of contractor	Value of Contract (in Rs.)	Scheduled date of completion of supplies / work	Payment details
	1	2	3	4	5	6	7	8	9	10	11	12	13.00	14	
SBU 33 (HIGHWAY/KOLKATA)															
13	17/LT/RITES /HW/KOL/RT330-00050/2019 Dt. 18/10/2019	Conducting NDT, Static Load Testing, Underwater Inspection, Rate Analysis, BoQ, Cost Estimate Including Traffic Diversion plan, Rehabilitation Measures, report Preparation, Inspection of test Results, Correlation of Theoretical and Field Result, Model Analysis Etc. For Bridge under South Zone of Public Works Directorate, Govt. of West Bengal.	Limited	18.10.2019	Single	01.11.2019	06no. tender recd.	1. M/s Struct Geotech Research Laboratories Pvt. Ltd, No.588,2nd Main,6th Block,Hosakerehalli Cross, Bansankari III Stage, II Phase, Bangalor - 560085, India. 2. M/s Cortex Construction Solution Private Limited, B-248 Basement, C.R. Park, New Delhi, Delhi 110019. 3. M/s Powergen Technical Services Pvt. Ltd., AD 189, 1st Floor, Salt Lake City, Sector-1, Kolkata- 700064. 4. M/s Structvel Designers & Consultants Pvt. Ltd., Structvel, Plot No. 15, Sector 24, Off Sion Panvel Highway, Turbhe, Navi Mumbai - 400705. 5. M/s Mythcon, Mahendra Enclave, Block - B, Space 4&5, AA - 32 Prafulla karanan -Kolkata - 700101, West Bengal, india. 6. M/s Amil Limited of Naimex House, A-8, Mohan Co-operative Industrial Estate, Mathura Road, New Delhi 110004, India.	NIL	Awarded	Work Order No. RITES/HW/KO L/RT330-00050/2019/10 91 on 15.11.2019	M/s Struct Geotech Research Laboratories Pvt. Ltd, No.588,2nd Main,6th Block,Hosakerehalli Cross, Bansankari III Stage, II Phase, Bangalor - 560085, India.	15,497,242.00	120 DAY DAYS FROM THE DATE OF ISSUE OF LoA	7th RA Bills paid on 13.01.2021
14	01/LT/RITES/HW/KOL/Geo Investigation Work/2021, Dated 13.01.2021	Geotechnical Investigation work for provision of additional services like Service Road, Truck lay Bye, PUP,VUP, FOB etc. for Augmenting Road Safety Features for Packag I: Dankuni-Chandamagar Section and Package II: Chandamagar - Mogra section of SH -13 in phase I: Part B: Detailed Design of Underpasses (VUP,LVUP), Pedestrian Underpasses (PUP)/Foot Over Bridges(FOBs).	E-Limited Tender	13.01.2021	Single	28.01.2021	4	1. FARGO CONSULTANTS PVT. LTD. 2. TECHNOMA(I). 3. GEO XEROX. 4. IDAX CONSULTANTING AND RESEARCH PVT. LTD.	1. FARGO CONSULTANTS PVT. LTD. 2. TECHNOMA(I). 3. IDAX CONSULTANTING AND RESEARCH PVT. LTD.	3. Geo-Xerox.	HW/KOL/WBHD CL/PH-1/Part-B/Geotechnical Investigation/2021/123	GEO XEROX, S-1, Mohinab Poral Lane, Salkia, Howrah, Westbengal, 711106.	464,853.00	01.04.2021	Nil